

Barrancas Avenue I/ Mitigation Pensacola, FL



Project Challenges	Solution	Support	Outcome
<ul style="list-style-type: none"> • URETEK contacted when other methods failed • Structure settled almost 12" due to inflow and infiltration • Pipe to structure joint failure • Structure and Pipes under water with high water flow • Night work 	<ul style="list-style-type: none"> • Inject using The URETEK Method directly through base of structure and invert of RCP to seal and stop soil migration • Where conventional methods failed URETEK stopped inflow and sealed joint in minutes 	<ul style="list-style-type: none"> • Designed injection port quantity and depth • Pre-construction meeting • On-site installation • Dewatered and plugged pipes to gain access to site 	<ul style="list-style-type: none"> • Minimal downtime: Work completed and lane reopened in 1 night • Stabilized soil supported structure • Pipe to structure joints sealed