

# CBRE Commercial Floor Leveling Portland, OR



Project Challenges	Solution	Support	Outcome
<ul style="list-style-type: none"> <li>Over time floors had settled up to 1 1/2 inches. Creating a very uneven surface through out office area.</li> <li>Previous repairs included expensive floor leveling with inconsistent and short-lived results.</li> </ul>	<ul style="list-style-type: none"> <li>Utilize URETEK Deep Injection® Process by injecting the 486Star structural polymer at predetermined locations to densify the support soil and lift the floor to grade.</li> <li>Floor lifted level and voids filled.</li> </ul>	<ul style="list-style-type: none"> <li>GPR was utilized for accurate determination of utilities.</li> <li>Perform work with little disruption to work environment.</li> </ul>	<ul style="list-style-type: none"> <li><b>No downtime:</b> All work performed in one day.</li> <li><b>No Service disruption</b></li> <li><b>Floor brought back into proper alignment.</b></li> </ul>