

Corporate Square – Office Building Knoxville, TN



Project Challenges	Solution	Support	Outcome
<ul style="list-style-type: none"> Settled foundations and slabs related to storm drainage issues. The stabilization scope was a key piece of a larger remediation and renovation project. Occupied building with sensitive equipment and information. Site conditions varied from project documents. 	<ul style="list-style-type: none"> Use the URETEK Deep Injection process to stabilize the foundations and improve the bearing capacity of the soils. Stabilize and lift the interior slabs using the URTEK Method. 	<ul style="list-style-type: none"> Pre-Bid Meeting with General Contractor and competing stabilization contractors. Designed injection quantity and depth Pre-construction meeting. On-site installation. 	<ul style="list-style-type: none"> Minimal intrusion: Work performed over one weekend. Cost Savings: Uretek performed the work for approximately 65% of the cost of helical piers /pressure grout. Soils stabilized: Soils stabilized to prevent future settlement.