

Northshore Elementary - Knoxville, TN

Foundation Stabilization and Slab Lifting



Project Challenges	Solution	Support	Outcome
<ul style="list-style-type: none">• Settlement of foundations and slabs in a section of a new school building under construction.• Bearing capacity of soils was reduced due to subsurface water flow. A 54" RCP storm line was removed during construction, but water continued to follow pipe bedding materials.	<ul style="list-style-type: none">• Stabilize foundations and thickened slabs using Uretex Deep Injection.• Fill voids and lift floating slabs using the Uretex Method.• Sheet piling (by others) was installed to cut off the flow of subsurface water outside of the footprint of the building.	<ul style="list-style-type: none">• Pre-Estimate site visit and meeting with general contractor.• Reviewed soils reports, structural and architectural drawings, and request for proposal.• Designed injection quantity and depth.	<ul style="list-style-type: none">• Minimal intrusion: Work performed in three days with no excavation and no delay to the construction schedule.• Soils stabilized: Soils stabilized to prevent future settlement in the foundations and slabs.• Slabs leveled: Slabs in classrooms were leveled to minimize floor leveling costs.