

SR 30 Double Box Culvert Stabilization

Navarre, FL



Project Challenges	Solution	Support	Outcome
<ul style="list-style-type: none"> Weak base soils surrounding a double box culvert caused settlement of right of way Stabilize roadway before scheduled resurfacing Anderson Columbia's schedule gave us a tight window to complete project on time 	<ul style="list-style-type: none"> Inject URETEK's polyurethane from surface to prevent migration of and stabilize weak base soils to prevent any subsidence of right of way. Injection casings installed at multiple locations and elevations. 	<ul style="list-style-type: none"> Designed injection points quantity and depth Pre-construction meeting with Hatch Mott MacDonald and Anderson Columbia On-site installation 	<ul style="list-style-type: none"> Minimal downtime: All work performed in two nights Stabilized soil: Mill and resurface work was completed with no delays