

Conagra Foods – Slab Stabilization

Dothan, AL



Project Challenges	Solution	Support	Outcome
<ul style="list-style-type: none"> Enclosed breezeway linking food processing building to finish goods warehouse had settled, causing forklift stability and safety concerns Transportation of finished goods inventory was affected Likely cause was poor roof drain collection system 	<ul style="list-style-type: none"> Inject polyurethane directly beneath settled portions of breezeway slab After soils were stabilized, a leveling compound was applied (by others) to provide smooth finish product 	<ul style="list-style-type: none"> Initial site visit Pre-Construction meeting with Owner's Rep and Subcontractor Injection Plan URETEK crew coordinated work within tight time frame coinciding with plant shutdown 	<ul style="list-style-type: none"> Requirement was to stabilize soft soils without lifting. Lifting slabs would have created problems with adjacent slab Actual injection time under 2 hours A completely satisfied Owner!