

# Tampa Riverwalk/MacDill Park

## Tampa, FL



| Project Challenges   | Solution   | Support  | Outcome  |
|--|--|--|--|
| <ul style="list-style-type: none"> <li>Two 10 ton concrete slabs and approximately 165' of walkway settled along the Hillsborough River seawall creating trip hazards.</li> <li>Limited time and site access to meet grand opening of completed City of Tampa Riverwalk</li> </ul> | <ul style="list-style-type: none"> <li>Utilize the URETEK Method to inject directly underneath the slab to lift seven areas back to grade</li> </ul> | <ul style="list-style-type: none"> <li>Coordination with City of Tampa Facilities Management</li> <li>Pre-construction meeting</li> <li>Ground Works' experienced crew prepped in less than 48 hours and completed project on a Sunday in 5 hours</li> <li>On-site installation</li> </ul> | <ul style="list-style-type: none"> <li>Five hour installation resulted in seven areas lifted back to grade at zero inconvenience to pedestrian traffic or construction work</li> <li>In addition, soil densified and joint sealed along seawall</li> </ul> |