

# Wells Fargo – Void Fill and Underseal

## West Palm Beach, FL



Project Challenges	Solution	Support	Outcome
<ul style="list-style-type: none"> <li>• 4' water line broke causing up to 1" voids throughout the 4,500 SF office space.</li> <li>• Void-fill and underseal 9" slab with wire mesh.</li> </ul>	<ul style="list-style-type: none"> <li>• Utilize multiple injection points to underseal the slab, and void fill</li> <li>• Utilize The URETEK Method throughout the problem areas.</li> </ul>	<ul style="list-style-type: none"> <li>• Self-designed solution based on site visits and Geotechnical findings by Ardaman and Associates and CBRE</li> <li>• During installation, monitored the injection process through laser equipment</li> </ul>	<ul style="list-style-type: none"> <li>• <b>Minimal intrusion:</b> Completed work in 1 day with no downtime or interruptions to customer's operations and construction.</li> <li>• <b>Customer Satisfaction:</b> Stabilized and filled voids to standards that helped exceed customer expectations.</li> </ul>